

Response to Anonymous Referee #1

In this document, the underlined part is those revision we made for a new manuscript.

Q1 (Question 1): General state of the art is well developed. However some references to works that deal with large areas inventories in Europe should be done (e.g. Van Den Eeckhaut, M., Hervás, J., 2012. State of the art of national landslide databases in Europe and their potential for assessing susceptibility, hazard and risk. *Geomorphology* 139 (140), 545–558.

Response 1 (R1): Thank you for your comment. In the new manuscript, we have investigated more literatures and provided more about landslide databases in Europe and their potential for assessing susceptibility, hazard and risk. The following underlined part has been added in the new manuscript.

A landslide inventory provides the basis for quantitative zoning of landslide susceptibility. Location, date, type, size, causal factors and damage are supposed to be included in this database. A commonly used landslide inventory does not yet appear but some regional or national landslide databases are now well developed. In Europe, currently 22 out of 37 contacted countries have national landslide databases, and six other countries only have regional landslide databases. Those national databases contain about 633,700 landslides in total, of which about 75% are in Italy, and more than 10,000 landslides are in Austria, the Czech Republic, France, Norway, Poland, Slovakia, and the UK. In these 37 European countries, only six have sufficient information to perform risk analysis and one to perform a hazard analysis, while 14 countries can carry out at least a susceptibility analysis. Therefore, at a continental scale landslide zoning seems to be limited to landslide susceptibility modelling only. Restricted access to the data also make it difficult for these data to be applied in scientific research. (Pg 2 Ln 25-36, the number in the clear version uploaded)

Q2: The authors should make clear what the added values of their study are. How a global landslide susceptibility map will be used for insurances that secure buildings in a local scale? Why the use of logistic regression which allow to weight each factor is important if a world map is presented and those weights will not be used in other areas?

R2: Thank you for your comment. The added value of this research is in the part of introduction and we have made it clearer. This paper addresses the gap in creating global landslide susceptibility maps using the widely used statistical method: logistic regression, and demonstrating the relative significance of different explanatory factors in global scale. (Pg 3 Ln 13-15) The global landslide susceptibility map in this paper is not for securing local buildings actually. For those international and national insurance or reinsurance companies, such map will provide them with clear knowledge of landslide hotspots at a macro level, which will help them concentrate on those susceptible areas and make relevant marketing strategies like transferring risks. (Pg 1 Ln 35-38) These underlined part has been added in the new manuscript.

Compared with some complex numerical methods like SVM, logistic regression provides a simple method to produce global landslide susceptibility map, which would be helpful in disseminating this research and could encourage further model development for its simplicity in modelling. What's more, the result from logistic regression could illustrate the relative importance of different factors in explaining landslides, which could not be achieved by SVM. (Pg 3 Ln 7-12) The accuracy of logistic regression model in this paper is quite high compared with that of similar experiment that is performed at national or local scale, which really exceeds expectation. To have one single model to explain the occurrence of past landslides events in global scale may be difficult, but the result of model in this paper shows that the factors and their weights in this research can actually provide good explanation of global landslide occurrence in one model. (Pg 9 Ln 21-26)

This is the reason why the method of logistic regression is used and it has been added in the new manuscript.

As for the weights of factor, actually they cannot provide adequate accuracy when building landslide model in local scale. However, we have determined to compare this research with those performed in local scale to investigate the rules of landslide occurrence in

different scales in the coming future. (Pg 9 Ln 30-33) We have added this part in the discussions.

Q3: The "inventory" section is in reviewer opinion the major weakness of the presented manuscript. Two general databases are combined and used: World Geological Hazard Inventory and NASA global landslide inventory. However, despite the references to the original sources some ideas should be clear in this manuscript as for example: a) what are the criteria that were used to recognize a landslide or to be inserted in the database; b) what is the best resolution? c) are criteria/resolution the same in both inventories? d) Sometimes that kind of inventories have a high degree of uncertainty in location. How you deal with "overlapping" of registries? e) What area the time-period of those inventories? f) It is not clear for me if authors (or the team of 10 persons) collect information in newspapers? And the literature what are the main sources? only peer review journals? Thesis? From which editors or universities? How many references are considered? Cross reference problems?

R3: Thank you for your comment. The landslide data in this research comes from BNU World Geological Hazard Inventory and NASA global landslide inventory. In the former manuscript, we did not provide adequate information about it. We have added more in this manuscript:

(1) The sources of related databases. The items in World Geological Hazard Inventory were collected manually from news reports (e.g. mass media in China, Xinhua News, and Sina News) and records in books and journals. We searched information about landslide on Internet by using keywords like landslide and debris flow. Then we read these descriptions carefully to determine whether it is a landslide and locate it, and later put it into the database. Thus the main source of World Geological Hazard Inventory can be news data. By investigating these news, we can find out those landslides that are of large volume or of high danger, for these kinds of landslides can be of high news value. (Pg 6 Ln 16-23)

The NASA global landslide inventory mainly collects landslides from several existing databases, including International Consortium on Landslides website (ICL; <http://iclhq.org>); International Landslide Centre, University of Durham (ILC; <http://www.landslidecentre.org>); The EM-DAT International Disaster Database (<http://www.em-dat.net>); International Federation of Red Cross and Red Crescent Societies field reports (<http://www.ifrc.org>); Reliefweb (<http://reliefweb.int>); humanitarian disaster information run by the United Nations Office for the Coordination of Humanitarian Affairs (OCHA); other online regional and national newspaper articles and media sources. (Pg 6 Ln 8-15)

The best resolution of World Geological Hazard Inventory is 0.001 degree, about 100m. (Pg 6 Ln 27) The NASA global landslide inventory 2km. (Pg 6 Ln 15-16)

(2) The time period of landslide database. In the World Geological Hazard Inventory, the earliest event can be dated to 1618. In this database, there is 117 landslides occurred before 1975, 84 between 1975 to 2000, and 274 between 2000 and 2014. The landslide events in the NASA global landslide inventory mainly happened in 2003, 2007, 2008 and 2009. Hence these two databases are complementary and they can be emerged to produce a more complete landslide database. (Pg 6 Ln 36-40) This part has been added in the new manuscript.

(3) The combination of two databases. When combining these two databases, the occurrence of time provides crucial standard. When two landslide events have different time (month), they are both reserved in the new database. If two events have the same occurrence time (month) and their locations are close, investigation through details in source could determine whether they are from the same disaster. If yes, the record with higher spatial resolution is reserved and the one with lower resolution is dropped. (Pg 6 Ln 30-34) This part has been added in the new manuscript.

Q4: A deep discussion should be done about how representative are these inventories. According to the authors 2005 landslides/debris flows are in the database, but for example in the work of Pereira et al. (2014) which use a historical landslide inventory based on press and reports in the northern region of a small country as Portugal, more than 600 cases were registered. Are the authors confident with 2005 registries for a World Wide

Map? In my opinion this is a strong weakness of this work. Pereira S, Zêzere JL, Quaresma ID, Bateira C (2014) Landslide incidence in the North of Portugal: Analysis of a historical landslide database based on press releases and technical reports. *Geomorphology* 214:514–525. doi:10.1016/j.geomorph.2014.02.032


R4: Thank you for your comment. We have read the paper of Pereira et al. The landslide data in that paper comes from press releases (regional and local newspapers) and technical reports (reports by civil protection authorities and academic works). The database contains 628 landslides with time period of 1900 to 2010. Pereira et al. also mentioned that regional and local newspapers are more effective than the national newspaper in reporting damaging landslides in the North of Portugal.

Compared with the research of Pereira et al., the amount of landslide records in our research seems not enough. However, landslides may have different magnitudes. The main focus of this research is global landslide susceptibility assessment, and hence the landslides in database of this research should be representative on global scale, i.e. having large volume or causing significant loss. The landslides in our database can meet such requirement and are either of large magnitudes or causing severe life loss or economic loss, which are hence easily reported by news agencies. The global landslide susceptibility map built on this database can inevitably underestimate the landslide susceptibility in some sparsely populated areas or less developed areas. However, if we don't following the guidelines, in our database there will be a large numbers of landslides that are occurred in countries with good landslide catalogue and few in countries with poor landslide catalogue. Such model may lead to overestimation of landslide susceptibility in countries with rich landslide records and underestimation of landslide susceptibility in countries with poor landslide records. This may not be good for improving the accuracy of the map of global landslide susceptibility. Hence we think that the landslide database in our research is relatively high in representative and reliable. We will explore the use of big data on Internet in building more comprehensive landslide database in our next research and tries to enhance the studies of landslide susceptibility when landslide catalogues from various countries can be easily accessed in the future. (Pg 9 Ln 34- Pg 10 Ln 4) Thank you for your recommendation.

Q5: Authors should try to compare subsets of their inventory with other national or “continental” ones (with higher detail and available in literature) to try to find if spatial overlay is acceptable. Some metric should be done.

R5: Thank you for your comment. These have been added in the new manuscript. In order to demonstrate the representative of landslide data used in this research, the landslide overlay in Europe of this research is compared with the spatial distribution of landslides in the study of Van Den Eeckhaut et al. (2012). As showed in Fig. 2, it is found that the spatial overlay of landslide samples in the research of European landslide susceptibility modelling is quite similar with that of the combined landslide database in this research. The landslides in Europe mainly distribute in mountainous areas like the Alps and the Balkan. (Pg 7 Ln 1-6)

Fig.2 Comparison of landslide overlay in this research and that in existing study



Q6: Considering figure 1 it seems that some areas are overestimated and that could be the result of the used inventories. In fact most of the dots are in Asia, and I believe that could be true, but it should be supported with statistical data from international databases, for example EM-DAT, used by UN. It seems to me that North Africa mountain ranges are underestimated;

A table with the number of landslides per region (for example continent or other wide regions that the authors consider adequate) in global inventory and in each data set used to model and validate will allow the reader to understand the how spatial representative are the data sets used. This should be inserted in results section;

R6: Thank you for your comment. In fact, the landslides in EM-DAT has been contained in our database. It is because EM-DAT is one important source of the NASA global landslide inventory and also the World Geological Hazard Inventory.

As for the samples in North Africa, thank you for reminding us on such issue. We have added a table in the part of results to illustrate the spatial representative of landslides in each continent in each dataset.

A table with the number of landslides in each continent in global inventory and in each data set used to model and validate is displayed, which will help readers understand how spatial representative the data sets used are (Table 5). It can be found that there is a small amount of landslide records in Africa. However, when either in the modelling process or validation process, different amount of landslides and non-landslides in African was selected. From Fig. 3 and Fig. 4, it is demonstrated that the results from every five datasets are relatively stable and high, which means the model built can be applied effectively in Africa. Otherwise, the results of five datasets may be different. (Pg 8 Ln 7-13)

Table 5 Numbers of landslides and non-landslides in each dataset.


Continent	Landslides	Dataset 1		Dataset 2		Dataset 3		Dataset 4		Dataset 5	
		Modelling (70%)	Validation (30%)	Modelling (70%)	Validation (30%)	Modelling (70%)	Validation (30%)	Modelling (70%)	Validation (30%)	Modelling (70%)	Validation (30%)
Asia	1205	847:348	358:163	848:394	357:157	838:383	367:155	849:364	356:162	847:393	358:165
Africa	69	55:317	14:129	50:307	19:114	47:324	22:130	47:315	22:129	49:302	20:126
Europe	121	94:211	27:70	86:212	35:116	87:200	34:91	88:206	33:88	85:251	36:106
North America	425	274:235	151:98	296:235	129:98	298:226	127:107	286:230	139:110	286:195	139:83
South America	133	93:189	40:98	86:174	47:75	99:179	34:78	97:193	36:80	96:144	37:64
Oceania	52	40:103	12:44	37:81	15:42	34:91	18:41	36:95	16:33	40:118	12:58
Total	2005	1403:1403	602:602	1403:1403	602:602	1403:1403	602:602	1403:1403	602:602	1403:1403	602:602

Numbers in left represent numbers of landslides, numbers in right represents numbers of non-landslides.


1
2 **Q7:** The first paragraph of Results section is mainly methodological procedure for
3 validation.
4 **R7:** Thank you for your comment. We agree that this part should be replaced and we have
5 adjusted it in the end of methodology and data in the new manuscript. Please refer to (Pg
6 7 Ln 22-27) in the newly revised manuscript.
7
8 **Q8:** Maybe the used inventories are biased by the scale of analysis and the adopted
9 recognition methodology (small movements disappear) or by the used criteria to consider
10 a landslide (for example only landslides that cause injuries). This and other assumptions
11 related to the inventories should be deeply discussed in Discussion section;
12 **R8:** Thank you for your comment. We believe that this comment is quite similar with Q4,
13 both about the representative of landslide inventories. Hence we have combined the
14 replies of these two comments. Please refer to (Pg 9 Ln 36- Pg 10 Ln 6) in the newly
15 revised manuscript for details.
16
17 **Q9:** Even if only a visual evaluation is possible to do: how different are the obtained results
18 when compared with other global landslide susceptibility maps (some of them referred in
19 this work)? And with other national/regional maps (for example, USA or Europe (Join
20 Research Center))?
21 **R9:** Thank you for your comment. We have added relevant comparison as follows. It can
22 be found in Pg 8 Ln 24-Pg 9 Ln 7.
23 The global landslide susceptibility map may be evaluated by comparison with four studies
24 from the current literature that focus on large-scale landslide susceptibility.
25 Comparing the European landslide susceptibility map drawn by Van Den Eeckhaut et al.
26 (2012) with the European part of susceptibility map in this study (Fig. 6 (a)), similar areas
27 of high landslide susceptibility can be observed. The former map includes two levels
28 (denoted High and Very High) as high susceptibility with a landslide probability of over 0.8,
29 and this study also includes two levels (Levels 4 and 5) as high susceptibility with a
30 probability over 0.7. The two maps have similar high susceptibility areas. Thus, for Europe,
31 landslide susceptibility map in this study agrees with existing related study.
32

1
2

Fig. 6 Comparison of existing studies with the related parts of this study



(a) Comparison of European landslide susceptibility map (from Van Den Eeckhaut et al. 2012) with the related part in this study's map



(b) Comparison of China landslide susceptibility map (from Liu et al. 2013) with the related part in this study's map

3

4 Comparing the Chinese landslide susceptibility map drawn by Liu et al. (2013)¹ with the
5 China part of susceptibility map in this study (Fig. 6 (b)), the former map includes two levels
6 (Levels 4 and 5) as susceptible with a landslide probability of over 0.6. Map in this study
7 includes three levels (denoted Levels 3, 4 and 5) as susceptible with landslide probability
8 of over 0.6. The main differences between the two maps are in the western Sichuan Basin
9 and southern Tibet, which is famous for its high elevation and intense relative relief. This
10 study applies many landslide cases in these areas. However, in the landslide database of
11 Liu et al. (2013), only a few landslides occur in these areas. This discrepancy is the reason
12 for the differences between the two maps.

13 As for landslide susceptibility at global scale, Nadim et al. (2006) and Hong et al. (2007)
14 have ever made magnificent efforts on such topic. One global landslide susceptibility map
15 (please refer to Fig. 7 in Nadim et al. (2006)) has five levels (Levels 5, 6, 7, 8 and 9) as
16 susceptible, while the map from this study includes three levels (Levels 3, 4 and 5) as

¹ Liu, C., Li, W., Wu, H., Lu, P., Sang, K., Sun, W., & Li, R. (2013). Susceptibility evaluation and mapping of China's landslides based on multi-source data. *Natural hazards*, 69(3), 1477-1495.

1 susceptible. In general, the susceptible areas of these two maps are fairly similar except
2 in Madagascar and the eastern Indo-China Peninsula.
3 Another global landslide susceptibility map (please refer to Fig. 3(a) in Hong et al. (2007))
4 has two levels (Levels 4 and 5) as susceptible, compared to map in this study, which has
5 three levels (Levels 3, 4 and 5) as susceptible. These two maps are similar over Asia,
6 Europe and Africa. However, it is noted that map of Hong et al. (2007) also differs from
7 map of this study in that it shows high landslide susceptibility in central and southern India,
8 and low landslide susceptibility in equatorial islands such as Malaysia, Indonesia, and the
9 Philippines. We believe that the classification of landslide susceptibility of this research can
10 be more scientific and closer to the existing conditions.

11
12 **Q10:** Page 3 line 33; Page 7 line 26 – please confirm the use of the term “topology”.
13 Topography? Please check the way how you performed in-text citations to several
14 references: sometimes they are alphabetically (e.g. page 2 line 5), others chronologically
15 (e.g. page 2 line 21) and others none of them (page 2 lines 17-18; page 3 line 25; page
16 4lines 15-16; page 5 lines 39-40; page 6 lines 14-15). Figures are adequate but in general
17 with low resolution.

18 **R10:** Thank you for your comment. We have revised those parts mentioned above. In the
19 new manuscript, we will provide figures with higher resolution. You can also find them in
20 the attachment of this response.

21
22 **Q11:** Figure 1 (in figure or caption) should include time-period of the inventory and a
23 reference to the main sources of the inventory. Each dot (triangle) means 1 landslide or
24 more? Please provide a similar graphical scale in figures 1 and 2. I suggest 0-2000 km.

25 **R11:** Thank you for your comment. The time period and data reference have been added
26 in Figure 1. Each dot represents one landslide. Similar graphical scale in Figures 1 and 5
27 (we believe that you refer to the table of global landslide susceptibility map produced by
28 this research, i.e. Fig. 4 not Fig. 2 in the old version, Fig. 5 in the new version) has also
29 been added. Please check the Figure 1 & 5 document in the attachment of this response.

30
31

1 **Response to Anonymous Referee #2**

2 In this document, the underlined part is those revision we made for a new manuscript.

3
4 **Question 1 (Q1):** By considering landslide triggering factors, this work is more like a
5 qualitative hazard mapping rather than a susceptibility mapping (van Westen, et al., 2008;
6 Nadim et al., 2008; Fell et al., 2008). van Westen, C. J., et al. (2008). "Spatial data for
7 landslide susceptibility, hazard, and vulnerability assessment: An overview." *Engineering*
8 *Geology* 102(3-4): 112-131. Nadim, F., et al. (2006). "Global landslide and avalanche
9 hotspots." *Landslides* 3(2): 159-173. Fell, R., et al. (2008). "Guidelines for landslide
10 susceptibility, hazard and risk zoning for land use planning." *Engineering Geology* 102(3-
11 4): 85-98.

12 **Response 1 (R1):** Thank you for your comment. In the paper of van Westen et al. (2008),
13 hazard assessment should include temporal and spatial probability of initiation,
14 magnitude–frequency relation and run out potential. Because we did not study the temporal
15 aspect of landslides, we hence did not use qualitative hazard mapping in this paper. On
16 the other, when investigating landslide models, there may not be explicit distinctions
17 between using the terms of susceptibility and hazard. For instance, in the paper of
18 Daneshvar (2014)², the intensity of precipitation is considered as a critical factor when
19 studying susceptibility, which influences the occurrence of landslides in semi-arid regions
20 despite the small interval between the minimum and maximum precipitation. Thank you for
21 your comment. We agree that our work is like a qualitative hazard mapping, but it is also
22 acceptable to use susceptibility mapping.

23
24 **Q2:** The slope gradient factor should be added, which is as important as relative relief.
25 Because, it is a common sense that steeper slopes are easier to have landslides than
26 gentler ones.

27 **R2:** Thank you for your comment. We agree that slope is very important factor in the
28 research of landslide susceptibility. We have included this factor when building landslide
29 model. But the result show that it is not statistically significant. Therefore we did not include
30 it in this paper. We have analysed the reason. At a global scale, factors such as elevation
31 and slope gradient can be replaced by topographic index or relative relief, which indicate
32 macroscopic differences in topography. Especially for landslide data with low location
33 precision, using factors such as elevation or slope gradient that precisely relate to landslide
34 location will reduce the accuracy of landslide susceptibility analysis. (Pg 3 Ln 42-Pg 4 Ln
35 2) This part has been added in the new manuscript.

36
37 **Q3:** In addition, land cover is also an important influencing factor on landslide susceptibility
38 mapping. It is well acknowledged that vegetation, especially trees can prevent some
39 shallow landslides. The authors are suggested to consider land cover types in their
40 mapping.

41 **R3:** Thank you for your comment. Like the factor of slope, we included the factor of land
42 cover when performing experiments. The land cover product with spatial resolution of 30m,

² Daneshvar, M. R. M. (2014). Landslide susceptibility zonation using analytical hierarchy process and gis for the bojnurd region, northeast of iran. *Landslides*, 11(6), 1079-1091.

1 GlobeLand30³, is produced by scientists in China and submitted to United Nations for
2 public use⁴. We tried this factor but found that it is not statistically significant and does not
3 improve the model accuracy. Hence the factor of land cover is not included in this paper.
4 The reason can be that comparing with other factors, land cover may not be a significantly
5 important factor in assessing landslide susceptibility in global scale.

6
7 **Q4:** The authors used two datasets for dependent variable. Is there any consistency
8 between them? Or, can you simply use them by combining both data sets? For example,
9 maybe the Chinese datasets has more landslides within China while underestimate
10 landslides abroad. Also, please introduce this new dataset in more detail, as there seems
11 to be rare reports of it before.

12 **R4:** Thank you for your comment. The landslide data in this research comes from BNU
13 World Geological Hazard Inventory and NASA global landslide inventory. In the former
14 manuscript, we did not provide adequate information about it. We have added more in this
15 manuscript:

16 (1)The sources of related databases. The items in World Geological Hazard Inventory were
17 collected manually from news reports (e.g. mass media in China, Xinhua News, and Sina
18 News) and records in books and journals. We searched information about landslide on
19 Internet by using keywords like landslide and debris flow. Then we read these descriptions
20 carefully to determine whether it is a landslide and locate it, and later put it into the
21 database. Thus the main source of World Geological Hazard Inventory can be news data.
22 By investigating these news, we can find out those landslides that are of large volume or
23 of high danger, for these kinds of landslides can be of high news value. (Pg 6 Ln 16-23)

24 The NASA global landslide inventory mainly collects landslides from several existing
25 databases, including International Consortium on Landslides website (ICL; <http://iclhq.org>);
26 International Landslide Centre, University of Durham (ILC; <http://www.landslidecentre.org>);
27 The EM-DAT International Disaster Database (<http://www.em-dat.net>); International
28 Federation of Red Cross and Red Crescent Societies field reports (<http://www.ifrc.org>);
29 Reliefweb (<http://reliefweb.int>); humanitarian disaster information run by the United Nations
30 Office for the Coordination of Humanitarian Affairs (OCHA); other online regional and
31 national newspaper articles and media sources. (Pg 6 Ln 8-15)

32 The best resolution of World Geological Hazard Inventory is 0.001 degree, about 100m.
33 (Pg 6 Ln 27) The NASA global landslide inventory 2km. (Pg 6 Ln 15-16)

34 (2) The time period of landslide database. In the World Geological Hazard Inventory, the
35 earliest event can be dated to 1618. In this database, there is 117 landslides occurred
36 before 1975, 84 between 1975 to 2000, and 274 between 2000 and 2014. The landslide
37 events in the NASA global landslide inventory mainly happened in 2003, 2007, 2008 and
38 2009. Hence these two databases are complementary and they can be emerged to
39 produce a more complete landslide database. (Pg 6 Ln 36-40) This part has been added in
40 the new manuscript.

41 (3) The combination of two databases. When combining these two databases, the
42 occurrence of time provides crucial standard. When two landslide events have different

³ <http://www.globeland30.org/GLC30Download/index.aspx>

⁴ <https://unstats.un.org/unsd/GlobeLand30.htm>


1 time (month), they are both reserved in the new database. If two events have the same
 2 occurrence time (month) and their locations are close, investigation through details in
 3 source could determine whether they are from the same disaster. If yes, the record with
 4 higher spatial resolution is reserved and the one with lower resolution is dropped. (Pg 6 Ln
 5 30-34) This part has been added in the new manuscript.

7 **Q5:** An improved discussion is needed to compare and highlight the contribution of this
 8 work in global landslide mapping compared to previous works.


9 **R5:** Thank you for your comment. We have added relevant comparison as follows. It can
 10 be found in **Pg 8 Ln 24-Pg 9 Ln 7**.

11 The global landslide susceptibility map may be evaluated by comparison with four studies
 12 from the current literature that focus on large-scale landslide susceptibility.
 13 Comparing the European landslide susceptibility map drawn by Van Den Eeckhaut et al.
 14 (2012) with the European part of susceptibility map in this study (Fig. 6 (a)), similar areas
 15 of high landslide susceptibility can be observed. The former map includes two levels
 16 (denoted High and Very High) as high susceptibility with a landslide probability of over 0.8,
 17 and this study also includes two levels (Levels 4 and 5) as high susceptibility with a
 18 probability over 0.7. The two maps have similar high susceptibility areas. Thus, for Europe,
 19 landslide susceptibility map in this study agrees with existing related study.

Fig. 6 Comparison of existing studies with the related parts of this study



(a) Comparison of European landslide susceptibility map (from Van Den Eeckhaut et al. 2012) with the related part in this study's map



1: 0.5 very low < 0.2; 2: 0.2 slow < 0.4; 3: 0.4 moderate < 0.6; 4: 0.6 high < 0.8; 5: 0.8 very high < 1.0

(b) Comparison of China landslide susceptibility map (from Liu et al. 2013)
with the related part in this study's map

1
2 Comparing the Chinese landslide susceptibility map drawn by Liu et al. (2013)⁵ with the
3 China part of susceptibility map in this study (Fig. 6 (b)), the former map includes two levels
4 (Levels 4 and 5) as susceptible with a landslide probability of over 0.6. Map in this study
5 includes three levels (denoted Levels 3, 4 and 5) as susceptible with landslide probability
6 of over 0.6. The main differences between the two maps are in the western Sichuan Basin
7 and southern Tibet, which is famous for its high elevation and intense relative relief. This
8 study applies many landslide cases in these areas. However, in the landslide database of
9 Liu et al. (2013), only a few landslides occur in these areas. This discrepancy is the reason
10 for the differences between the two maps.
11 As for landslide susceptibility at global scale, Nadim et al. (2006) and Hong et al. (2007)
12 have ever made magnificent efforts on such topic. One global landslide susceptibility map
13 (please refer to Fig. 7 in Nadim et al. (2006)) has five levels (Levels 5, 6, 7, 8 and 9) as
14 susceptible, while the map from this study includes three levels (Levels 3, 4 and 5) as
15 susceptible. In general, the susceptible areas of these two maps are fairly similar except
16 in Madagascar and the eastern Indo-China Peninsula.
17 Another global landslide susceptibility map (please refer to Fig. 3(a) in Hong et al. (2007))
18 has two levels (Levels 4 and 5) as susceptible, compared to map in this study, which has
19 three levels (Levels 3, 4 and 5) as susceptible. These two maps are similar over Asia,
20 Europe and Africa. However, it is noted that map of Hong et al. (2007) also differs from
21 map of this study in that it shows high landslide susceptibility in central and southern India,
22 and low landslide susceptibility in equatorial islands such as Malaysia, Indonesia, and the
23 Philippines. We believe that the classification of landslide susceptibility of this research can
24 be more scientific and closer to the existing conditions.
25
26
27

⁵ Liu, C., Li, W., Wu, H., Lu, P., Sang, K., Sun, W., & Li, R. (2013). Susceptibility evaluation and mapping of China's landslides based on multi-source data. *Natural hazards*, 69(3), 1477-1495.

1 Landslide susceptibility mapping on global scale using method
2 of logistic regression

3
4 Le Lin^{1,2} Qigen Lin^{1,2} Ying Wang^{1,2}

5 ¹Key Laboratory of Environmental Change and Natural Disaster of MOE, Beijing Normal University, No.19,
6 XinJieKouWai St., HaiDian District, 100875, Beijing, China

7 ²Academy of Disaster Reduction and Emergency Management, Beijing Normal University, No.19, XinJieKouWai
8 St., HaiDian District, 100875, Beijing, China

9 Correspondence to: Ying Wang (wy@bnu.edu.cn)

10

11 **Abstract.** This paper proposes a statistical model for mapping global landslide susceptibility based on
12 logistic regression. After investigating explanatory factors for landslides in the existing literature, five
13 factors were selected to model landslide susceptibility: relative relief, extreme precipitation, lithology,
14 ground motion and soil moisture. When building model, 70% of landslide and non-landslide points were
15 randomly selected for logistic regression, and the others were used for model validation. For evaluating
16 the accuracy of predictive models, this paper adopts several criteria including receiver operating
17 characteristic (ROC) curve method. Logistic regression experiments found all five factors to be
18 significant in explaining landslide occurrence on global scale. During the modeling process, percentage
19 correct in confusion matrix of landslide classification was approximately 80% and the area under the
20 curve (AUC) was nearly 0.87. During the validation process, the above statistics were about 81% and
21 0.88, respectively. Such result indicates that the model has strong robustness and stable performance.
22 This model found that at a global scale, soil moisture can be dominant in the occurrence of landslides
23 and topographic factor may be secondary.

24

25 **Keywords**

26 global scale; landslide susceptibility mapping; explanatory factors; logistic regression

27

28 **1. Introduction**

29 Landslides are a pervasive natural hazard, causing significant casualties and economic loss around the
30 world (Budimir et al., 2015). Major news websites and online blogs from experts (such as The Landslide
31 Blog, a thematic blog maintained by Prof. Dave Petley at the University of East Anglia) show that
32 landslides almost occur every day. It is important and necessary to find out where the global landslide
33 hotspot areas are and what factors can influence the occurrence of landslides. Such information would
34 provide crucial reference for researchers and decision makers in some industries like insurance, and
35 project managers in some non-governmental organizations (NGO). For those international and national
36 insurance or reinsurance companies, such map will provide them with clear knowledge of landslide
37 hotspots at a macro level, which will help them concentrate on those susceptible areas and make relevant
38 marketing strategies like transferring risks (Bednarik et al., 2010). Geographers can also find it interesting
39 for revealing spatial pattern of landslide distribution. To answer these questions, studies of global
40 landslide susceptibility are required. Such research will help give a global perspective on landslides,
41 which may encourage international cooperation for disaster risk reduction.

42 At present, research methods for landslide susceptibility mapping can be divided into three major

批注 [LL1]: Reviewer #1, R2

1 categories, qualitative factor overlay, statistical models and geotechnical process models (Dai and Lee,
2 2002). Generally, geotechnical process methods are developed from slope stability analyses and are
3 applicable for site-specific landslides or when the ground conditions are quite uniform in the study area.
4 Also, this method requires the landslide types to be known and relatively easy for analysis (Terlien et al.,
5 1995; Wu and Sidle, 1995), and hence it is seldom used in large-scale landslide susceptibility mapping.
6 In qualitative methods, landslide experts select landslide controlling factors and combine these factors
7 into a susceptibility map, based on their knowledge and experience of landslide investigation.
8 (Anbalagan, 1992; Pachauri and Pant, 1992). In contrast, statistical methods include statistical
9 determination into combinations of explanatory factors (Carrara et al., 1991; Dhakal et al., 1999).
10 Among these three types of methodologies, the latter two are widely applied in large-scale landslide
11 susceptibility mapping. Relatively, reproducibility of results and subjectivity in landslide modelling can
12 be the apparent disadvantages of the method of qualitative factor overlay. In recent time, large volumes
13 of landslide inventories and multi-source data of landslide factors are gradually accessible to researchers
14 and that make statistical methods are frequently used in landslide susceptibility mapping.

15 In statistical methods, Logistic regression model has been frequently used in geological hazard
16 research and employed to explore the factors that influences landslides and determine landslide
17 probability (Ayalew and Yamagishi, 2005; Van Den Eeckhaut et al., 2006). Compared with other
18 statistical approaches, Brenning (2005) found that logistic regression models have a relatively low rate
19 of error. Logistic regression can include dichotomous dependent variables (e.g. whether a landslide
20 occurred) and independent variables, as well as categorical or continuous variables (Chang et al., 2007;
21 Atkinson and Massari, 1998). The fact that landslide explanatory factors can be included in the model as
22 either categorical or continuous variables gives logistic regression models a great advantage over
23 multiple regression models, which can only include continuous variables. Finally, logistic regression
24 models can be used to draw susceptibility maps when combined with GIS (Lee, 2005; Bai et al., 2010).

25 A landslide inventory provides the basis for quantitative zoning of landslide susceptibility. Location,
26 date, type, size, causal factors and damage are supposed to be included in this database. A commonly
27 used landslide inventory does not yet appear but some regional or national landslide databases are now
28 well developed. In Europe, currently 22 out of 37 contacted countries have national landslide databases,
29 and six other countries only have regional landslide databases. Those national databases contain about
30 633,700 landslides in total, of which about 75% are in Italy, and more than 10,000 landslides are in
31 Austria, the Czech Republic, France, Norway, Poland, Slovakia, and the UK. In these 37 European
32 countries, only six have sufficient information to perform risk analysis and one to perform a hazard
33 analysis, while 14 countries can carry out at least a susceptibility analysis. Therefore, at a continental
34 scale landslide zoning seems to be limited to landslide susceptibility modelling only. Restricted access
35 to the data also make it difficult for these data to be applied in scientific research (Van Den Eeckhaut,
36 and Hervé, 2012).

37 In the existing literature, there are few studies of landslide susceptibility that were carried out on a
38 global scale; those that exist mainly used qualitative or semi-qualitative methodologies. For example,
39 Mora and Vahrson (1994) proposed a method for assessing landslide susceptibility in tropical earthquake-
40 prone areas that included three fundamental factors (slope, soil moisture, and lithology) and two
41 triggering factors (extreme precipitation and ground motion). Nadim et al. (2006) applied the research of
42 Mora and Vahrson (1994) to assess global landslide susceptibility and risk. Hong et al. (2007) selected
43 six influencing factors (slope, elevation, soil type, soil texture, land cover type and drainage density) in
44 the model of weighted linear combination (WLC). To obtain optimal weights combination, they tried

批注 [LL2]: Reviewer #1, R1

1 different combination of factor weights to make model results similar with the existing landslide
2 susceptibility map of the USA. Finally, they drew a global landslide susceptibility map using the weights
3 combination obtained above. Some scholars have also attempted to study global landslides with statistical
4 methods. Farahmand and AghaKouchak (2013) used a global landslide inventory compiled by the
5 National Aeronautics and Space Administration (NASA) to build a global landslide susceptibility model
6 based on the method of Support Vector Machine (SVM) that includes three variables, satellite-sensed
7 precipitation, digital elevation model (DEM) and land cover type. Compared with some complex
8 numerical methods like SVM, logistic regression provides a simple method to produce global landslide
9 susceptibility map, which would be helpful in disseminating this research and could encourage further
10 model development for its simplicity in modeling. What's more, the result from logistic regression could
11 illustrate the relative importance of different factors in explaining landslides, which could not be achieved
12 by some complex numerical methods like SVM.

批注 [LL3]: Reviewer #1, R2

13 This paper addresses the gap in creating global landslide susceptibility maps using the widely used
14 statistical method: logistic regression, and demonstrating the relative significance of different
15 explanatory factors in global scale. In this paper, a global landslide inventory database is constructed and
16 used for building a stepwise logistic regression model to evaluate global landslide susceptibility. Finally,
17 a global landslide susceptibility map that visualizes this model is produced. In the landslide susceptibility
18 model, five factors (extreme precipitation, soil moisture, lithology, relative relief and ground motion) are
19 included as explanatory factors in stepwise logistic regression. In total, 70% of landslide and non-
20 landslide events are randomly selected for logistic regression and the rest are used for model validation.
21 It is found that such model has good explanatory power and performs well in model prediction. Landslide
22 explanatory factors and the extent to which these factors influence landslide occurrence can be derived
23 from model results directly without expert experience, which are rare in statistical assessment of global
24 landslide susceptibility.

批注 [LL4]: Reviewer #1, R2

26 2. Explanatory factors

27 When assessing landslide susceptibility, the selection of explanatory factors is essential and significant.
28 Typical explanatory factors from previous work (Table 1) fall into seven general categories, including
29 topography, geology, hydrology, soil, precipitation, land cover and ground motion. Generally speaking,
30 explanatory factors for landslides can be divided into fundamental factors and triggering factors (Nadim
31 et al., 2006). Fundamental factors include environmental conditions that generate the potential of
32 landslide occurrence, such as topography, lithology and soil. Triggering factors explain direct effects that
33 drive slope instability, such as ground motion and extreme precipitation. In existing literatures,
34 combination of trigger and susceptibility can influence landslide hazard level (Nadim et al., 2006).
35 However, landslide model without landslide information like time and magnitude (like size, speed,
36 kinetic energy or momentum of mass) cannot be correctly defined as hazard models (Guzzetti et al.,
37 1999). Hence, in this paper, both fundamental factors and triggering factors are included to evaluate
38 landslide susceptibility.

39 In existing studies of landslides at a regional scale, topography is regarded as a powerful explanatory
40 factor for the occurrence of landslides (Dai and Lee, 2002; Lee and Min, 2001), and it is also
41 demonstrated at a global scale (Hong et al., 2007). For most studies, topography includes relief
42 characteristics such as elevation, slope gradient and slope aspect. At a global scale, factors such as
43 elevation and slope gradient can be replaced by topographic index or relative relief, which indicate
44 macroscopic differences in topography. Especially for landslide data with low location precision, using

1 factors such as elevation or slope gradient that precisely relate to landslide location will reduce the
2 accuracy of landslide susceptibility analysis (Farahmand and AghaKouchak, 2013). Therefore, a general
3 factor such as relative relief is more appropriate, and in this paper, relative relief is used to represent
4 **topology/topography**. Relative relief is defined as the difference between maximum and minimum
5 elevation values within an area (Chauhan et al., 2010). Relative relief has been shown to be an important
6 explanatory factor, and landslide occurrence is generally higher in high relative relief areas (Anbalagan,
7 1992).

8 For geology, attributes like rock age and rock type can be chosen, with data mainly coming from small
9 regional geological surveys and field studies. Studies of global landslide susceptibility have shown that
10 lithology is a fundamental factor (Nadim et al., 2006). Landslides are more likely to occur in some
11 relatively later formed rocks with lower intensity and less likely in relatively earlier formed rocks with
12 sufficient solidification and high intensity. Hence the factor of lithology is included in landslide model.

13 The water condition of the land surface also affects landslides. With the development of large data
14 sharing frameworks for meteorological data, precipitation information is easily available and hence
15 frequently used in landslide analysis (Farahmand and AghaKouchak, 2013). However, as Nadim et al.
16 (2006) propose, soil moisture also can be proxy of water condition for it represents average moisture
17 condition of the soil. Compared with mean annual precipitation, it can avoid the interruption of extreme
18 precipitation, which can objectively reflect the possibility of slope instability in long period and can be
19 taken as fundamental factor of landslide occurrence. Farahmand and AghaKouchak (2013) also
20 recommend the use of soil moisture data in study of global landslide susceptibility. Therefore, soil
21 moisture as an explanatory factor is adopted in this paper.

22 Ground motion and extreme precipitation are always analyzed as triggering factors of landslides, using
23 data from field surveys and monitoring observations. Landslides are generally triggered by earthquakes
24 or by heavy precipitation. Strong ground motion during earthquakes cause rocks to rupture, thus inducing
25 landslides. As for rainfalls, rain and/or meltwater that reaches the ground surface infiltrates into the
26 ground and forms groundwater. During this process, the pressure of the water that fills the void spaces
27 between soil particles and rock fissures rises when the amount of water infiltrating into the ground
28 increases. A rise in pore-water pressure causes a drop in effective stress, affecting the stability of a slope,
29 and thus is a major cause of landslides and other sediment-related disasters (Matsuura et al., 2008).
30 Intense rainfall is believed to be a cause of shallow landslides (Caine, 1980). Current studies of landslides
31 consider ground motion and extreme precipitation as triggering factors (Umar et al., 2014; Nowicki et
32 al., 2014; Nadim et al., 2006). Therefore, in this paper, ground motion and monthly extreme precipitation
33 are used as triggering factors. In summary, this paper uses relative relief, soil moisture, lithology, monthly
34 extreme precipitation and PGA as explanatory factors for global scale landslide susceptibility. The first
35 three are fundamental factors, and the last two are triggering factors.

37 **3. Methodology and Data**

38 **3.1 Study area**

39 This paper considers global continental areas from 72 °N to 72 °S, excluding Greenland and the Antarctic
40 continent. Because this research is specific to terrestrial landslides, oceans and areas covered by glaciers
41 or ice sheets are excluded. The scope of this paper is also limited by data coverage for explanatory factors.
42 As the coverage area of lithology is from 72 °N to 72 °S, therefore, the final susceptibility map is limited
43 to such boundary.

44 **3.2 Logistic regression model**

批注 [LL5]: Reviewer #2, R2

批注 [LL6]: Reviewer #1, R10

1 What's more, Logistic regression models are commonly fitted in a stepwise manner (Budimir et al., 2015).

2 The general form of a logistic regression model is as follows:

$$3 \quad \text{logit}(y) = \beta_0 + \beta_1 x_1 + \beta_2 x_2 + \dots + \beta_i x_i + e \quad (1)$$

4 In Eq. 1, y is the dependent variable that reflects landslide occurrence, x_i is the independent variable
5 related to explanatory factors, β_0 is a constant, β_i is the regression coefficient for the explanatory factors,
6 and e is the random error. The probability p of the dependent variable y can be expressed as follows in
7 Eq. 2:

$$8 \quad p = \frac{\exp(\beta_0 + \beta_1 x_1 + \beta_2 x_2 + \dots + \beta_i x_i)}{1 + \exp(\beta_0 + \beta_1 x_1 + \beta_2 x_2 + \dots + \beta_i x_i)} \quad (2)$$

9 **3.3 Independent variables**

10 In this paper, explanatory factors are put into stepwise logistic regression model as independent variables.
11 All layer data of these explanatory factors are converted to the WGS 1984 geographical coordinate
12 system. Original resolution of factors is reserved as simple resampling cannot make real contribution to
13 the accuracy and precision of information provided in the layers.

14 Topographic data come from GTOPO30 (USGS, 2012), which is a global elevation dataset from Earth
15 Resources Observation and Science (EROS) Center. Its spatial resolution is 30 arc-seconds
16 (approximately 1 kilometer), and it covers the earth surface from 90 °N to 90 °S and 180 °E to 180 °W.
17 After obtaining the data, relative relief is calculated by a moving window method in ArcGIS with window
18 size of 0.5 arc-degree. From existing literatures, there is few statement about proper classification method
19 of relative relief. Relative relief is hence divided into 10 types with successive ordinal values from 1 to
20 10, using the natural breaks method of classification (Table 2).

21 Lithology data come from a geological map of the world at a 1:25,000,000 scale (the third version)
22 published by the Commission for the Geological Map of the World (CGMW, 2010) and UNESCO. In
23 the Mercator projection, the north and south boundaries of this map are set as 72 °N and 72 °S. As a
24 consequence, a large extent of the Antarctic continental coastline is visible, with a better delimitation of
25 the Southern Ocean. The southern half of Greenland is also visible (Bouysse, 2010). The lithology data
26 are rasterized with a spatial resolution of 0.01 °. Following Nadim et al. (2006), global lithology data can
27 be divided into 6 categories (Table 2). The spatial resolution of 0.01 ° was used because the primary
28 electronic map is vector-based. Its information can be greatly reserved by using small-scale raster when
29 converted into raster map, and a small-scale raster can fit the coastline well.

30 In this paper, the soil moisture index is used to represent the local soil humidity level. With data
31 products from the Center for Climatic Research at the University of Delaware, Willmott and Feddema
32 (1992) proposed a new soil moisture index. In this index, soil moisture was normalized to a range from
33 -1.0 to 1.0 with a spatial resolution of 0.5 °. Nadim et al. (2006) classified soil moisture data into levels
34 from 1 to 5 (Table 2), with higher values indicating greater humidity.

35 Monthly extreme precipitation with a repeat period of 100 years is calculated using historical
36 precipitation grid data over 50 years (from 1961 to 2010) from the GPCC Full Data Reanalysis
37 (Schneider et al., 2011). As no typical classification method for extreme precipitation exists in literatures,
38 this precipitation data is divided into 10 levels (Table 2) with a spatial resolution of 0.5 °, according to
39 the natural breaks classification method.

40 For ground motion, PGA with an exceedance probability of 10% over 50 years is included (that is, a
41 repeat period of 475 years). Data are from the global seismic hazard map created by the Global Seismic
42 Hazard Assessment Program (GSHAP) of the International Lithosphere Program (ILP). The map shows
43 PGA with an exceedance probability of 10% over 50 years and a spatial resolution of 0.1 ° (Giardini et

1 al., 2003). Based on the methodology of Nadim et al. (2006), PGA can be divided into 10 levels (Table
2 2), with higher values denoting greater seismic hazard.

3 3.4 Dependent variables

4 The dependent variables that enter the model are global landslide inventory data and simulated non-
5 landslide data.

6 This paper uses global landslide inventory data from a combined database. This database stores
7 landslide information of two existing inventories: World Geological Hazard Inventory created by the
8 Academy of Disaster Reduction and Emergency Management of Beijing Normal University (ADREM,
9 BNU), and NASA global landslide inventory (refer to Kirschbaum et al. 2010 for details). The NASA
10 global landslide inventory mainly collects landslides from several existing databases, including
11 International Consortium on Landslides website (ICL; <http://iclhq.org>); International Landslide Centre,
12 University of Durham (ILC; <http://www.landslidecentre.org>); The EM-DAT International Disaster
13 Database (<http://www.em-dat.net>); International Federation of Red Cross and Red Crescent Societies
14 field reports (<http://www.ifrc.org>); Reliefweb (<http://reliefweb.int>); humanitarian disaster information
15 run by the United Nations Office for the Coordination of Humanitarian Affairs (OCHA); other online
16 regional and national newspaper articles and media sources. The best resolution of the NASA global
17 landslide inventory is 2 km. The items in World Geological Hazard Inventory were collected manually
18 from news reports (e.g. mass media in China, Xinhua News, and Sina News) and records in books and
19 journals (e.g. Galli and Guzzetti, 2007 and Gao, 1999). We searched information about landslide on
20 Internet by using keywords like landslide and debris flow. Then we read these descriptions carefully to
21 determine whether it is a landslide and locate it, and later put it into the database. Thus the main source
22 of World Geological Hazard Inventory can be news data. By investigating these news, we can find out
23 those landslides that are of large volume or of high danger, for these kinds of landslides can be of high
24 news value. A large range of literatures, not only reviewed academic books and journals but also
25 newspaper and local chronicles, was included to serve as the information sources so as to investigate
26 those geological hazards which happened long time ago or in remote area. Such rich information
27 sources can provide as more landslides as possible to reduce the uncertainty brought by limited landslide
28 database. The best resolution of World Geological Hazard Inventory is 0.001 degree, about 100m. Two
29 teams were assigned to develop and maintain this inventory. One team (about 10 persons) was
30 responsible for collecting information from literatures and the other team (about 4 persons) was expected
31 to check and review the items collected for data quality control. When combining these two databases,
32 the occurrence of time provides crucial standard. When two landslide events have different time (month),
33 they are both reserved in the new database. If two events have the same occurrence time (month) and
34 their locations are close, investigation through details in source could determine whether they are from
35 the same disaster. If yes, the record with higher spatial resolution is reserved and the one with lower
36 resolution is dropped. Example of this inventory can be found in Table 3.

37 In the World Geological Hazard Inventory, the earliest event can be dated to 1618. In this database,
38 there is 117 landslides occurred before 1975, 84 between 1975 to 2000, and 274 between 2000 and 2014.
39 The landslide events in the NASA global landslide inventory mainly happened in 2003, 2007, 2008 and
40 2009. Hence these two databases are complementary and they can be emerged to produce a more
41 complete landslide database. In all, the combined database stores landslide information like hazard type,
42 occurrence time, location (including geographical coordinates and locating precision), fatalities and data
43 sources. Currently, this database contains 2005 landslides, their location as showed in Fig. 1. This
44 combined database includes landslides (debris slides, rotational slides, and slumps) and debris flows,

批注 [LL7]: Reviewer #1, R3(1); Reviewer #2, R4(1)

批注 [LL8]: Reviewer #1, R3(1); Reviewer #2, R4(1)

批注 [LL9]: Reviewer #1, R3(1); Reviewer #2, R4(1)

批注 [LL10]: Reviewer #1, R3(1); Reviewer #2, R4(1)

批注 [LL11]: Reviewer #1, R3(3), Reviewer #2, R4(3)

批注 [LL12]: Reviewer #1, R3(2); Reviewer #2, R4(2)

1 following the landslide classification of Varnes (1984) and Cruden and Varnes (1996).

2 In order to demonstrate the representative of landslide data used in this research, the landslide overlay
3 in Europe of this research is compared with the spatial distribution of landslides in the study of Van Den
4 Eeckhaut et al. (2012). As showed in Fig. 2, it is found that the spatial overlay of landslide samples in
5 the research of European landslide susceptibility modelling is quite similar with that of the combined
6 landslide database in this research. The landslides in Europe mainly distribute in mountainous areas like
7 the Alps and the Balkan.

批注 [LL13]: Reviewer #1, R5

8 Non-landslide events come from generating random points. Because landslide location accuracy is
9 approximately 0.25°, a buffer zone is created around the existing landslide points with a radius of 0.25°
10 to represent the location range of each landslide event. The buffer zone is then removed from the global
11 continent area and the other part on global continent forms potential non-landslide area. The quantity of
12 non-landslide points should be carefully considered. Most studies use an equal amount of landslide points
13 and non-landslide points (Dai and Lee, 2002; Kawabata and Bandibas, 2009; Chau and Chan, 2005;
14 Costanzo et al., 2014; Regmi et al., 2014; Mathew et al., 2009). However, a few authors prefer an unequal
15 amount (Van Den Eeckhaut et al., 2012; Felicisimo et al., 2013). For example, Van Den Eeckhaut et al.
16 (2006) use 5 times as many non-landslide cells as landslide cells, and Farahmand and AghaKouchak
17 (2013) use 10 times as many non-landslide cells as landslide cells. In order to make sensitivity test on
18 the landslide susceptibility model in the paper and also reduce the uncertainty included by random non-
19 landslide, 5 non-landslide sets which each had equal number as landslides were created using random
20 sampling without replacement. To validate the landslide model, method of splitting datasets is applied
21 (Van Den Eeckhaut et al., 2012). For each dataset, 70% of landslide and non-landslide are randomly
22 selected for modeling, and the remaining 30% are used for validation.

23 Confusion matrix and Akaike's information criterion value (AIC) (Allison, 2001; Van Den Eeckhaut
24 et al., 2006) are applied to assess model performance. In addition, this paper also adopts a receiver
25 operating characteristic (ROC) curve to evaluate model effectiveness. The ROC curve helps to validate
26 a model graphically (Swets, 1988), providing an analysis based on true-positive and false-positive rates.
27 With higher area under this curve (AUC), such model is demonstrated to perform well in prediction
28 (Mathew et al., 2009).

批注 [LL14]: Reviewer #1, R7

30 4. Results

31 ~~Stepwise logistic regression is applied to analyze each dataset. Confusion matrix and Akaike's~~
32 ~~information criterion value (AIC) (Allison, 2001; Van Den Eeckhaut et al., 2006) are applied to assess~~
33 ~~model performance. In addition, this paper also adopts a receiver operating characteristic (ROC) curve~~
34 ~~to evaluate model effectiveness. The ROC curve helps to validate a model graphically (Swets, 1988),~~
35 ~~providing an analysis based on true positive and false positive rates. With higher area under this curve~~
36 ~~(AUC), such model is demonstrated to perform well in prediction (Mathew et al., 2009).~~ The results and
37 validation of the logistic regression models for 5 datasets are shown in Table 4.

38 It is found that among these 5 datasets, percentage correct in confusion matrix ranges from 78.7% to
39 80.4% during the modeling process and from 79.9% to 82.1% during the validation process. Generally,
40 the logistic regression models in this study show high accuracy in confusion matrix. For the 5 datasets,
41 their AUC values range from 0.8685 to 0.8846 when modeling (Fig. 23) and from 0.8809 to 0.8933 when
42 validating (Fig. 34). On average, the AUC value in the logistic regression model is approximately 0.88,
43 which indicates a relatively great performance in prediction.

带格式的: 缩进: 首行缩进: 0 字符

44 By using the principle of high percentage correct in confusion matrix, high AUC value and low AIC

1 value, the regression model from dataset 2 was selected as the global landslide susceptibility model. This
2 model is then used to analyze the importance of the explanatory factors on landslides and employed in
3 landslide susceptibility mapping. The formula of the best model is as follows:

$$\begin{cases} P = \frac{f}{1+f} \\ f = \text{Exp}(-5.7047 + 0.5528 * S + 0.1958 * A + 0.1245 * L + 0.3159 * R + 0.2957 * E) \end{cases} \quad (3)$$

4
5
6
7
8 where P stands for the probability of landslides, and S, A, L, R, and E stand for landslide explanatory
9 factors of soil moisture, PGA, lithology, relative relief and extreme precipitation, respectively.

10 In the model above, all variables are significant at the 1% confidence level. The coefficients of each
11 factor show that the greatest contribution to landslide occurrence comes from soil moisture, which has a
12 coefficient of approximately 0.6. The next most important factors are relative relief and extreme
13 precipitation, with coefficients of approximately 0.3. The contribution of PGA and lithology is relatively
14 low, with a coefficient of approximately 0.2 and 0.1.

15 [A table with the number of landslides in each continent in global inventory and in each data set used](#)
16 [to model and validate is displayed, which will help readers understand how spatial representative the](#)
17 [data sets used are \(Table 5\). It can be found that there is a small amount of landslide records in Africa.](#)
18 [However, when either in the modelling process or validation process, different amount of landslides and](#)
19 [non-landslides in African was selected. From Fig. 3 and Fig. 4, it is demonstrated that the results from](#)
20 [every five datasets are relatively stable and high, which means the model built can be applied effectively](#)
21 [in Africa. Otherwise, the results of five datasets may be different.](#)

22 A global landslide susceptibility map can be drawn using the model in Eq. 3. Based on existing
23 susceptibility classification methods from Guzzetti et al. (2006), Van den Eeckhaut et al. (2012), this
24 map classifies susceptibility levels according to breakpoints of 0.4, 0.6, 0.7 and 0.9. These breakpoints
25 define a susceptibility map with 5 levels, i.e. very low, low, moderate, high, very high (Fig. 45).

26 The susceptibility map shows that global landslide hotspots are the Alps, the Iranian Plateau, the
27 Pamirs, the southern Qinghai-Tibet Plateau, the mountainous region of southwestern China, the islands
28 in the western Pacific Ocean, including Japan, the Philippines, Malaysia, Indonesia and New Zealand,
29 northeastern North America, Central America and the Andes in South America.

30 31 5. Discussion

32 [The global landslide susceptibility map may be evaluated by comparison with four studies from the](#)
33 [current literature that focus on large-scale landslide susceptibility.](#)

34 [Comparing the European landslide susceptibility map drawn by Van Den Eeckhaut et al. \(2012\) with](#)
35 [the European part of susceptibility map in this study \(Fig. 6 \(a\)\), similar areas of high landslide](#)
36 [susceptibility can be observed. The former map includes two levels \(denoted High and Very High\) as](#)
37 [high susceptibility with a landslide probability of over 0.8, and this study also includes two levels \(Levels](#)
38 [4 and 5\) as high susceptibility with a probability over 0.7. The two maps have similar high susceptibility](#)
39 [areas. Thus, for Europe, landslide susceptibility map in this study agrees with existing related study.](#)

40 [Comparing the Chinese landslide susceptibility map drawn by Liu et al. \(2013\) with the China part of](#)
41 [susceptibility map in this study \(Fig. 6 \(b\)\), the former map includes two levels \(Levels 4 and 5\) as](#)
42 [susceptible with a landslide probability of over 0.6. Map in this study includes three levels \(denoted](#)
43 [Levels 3, 4 and 5\) as susceptible with landslide probability of over 0.6. The main differences between](#)

带格式的: 缩进: 首行缩进: 1 字符

批注 [LL15]: Reviewer #1, R6

1 the two maps are in the western Sichuan Basin and southern Tibet, which is famous for its high elevation
2 and intense relative relief. This study applies many landslide cases in these areas. However, in the
3 landslide database of Liu et al. (2013), only a few landslides occur in these areas. This discrepancy is the
4 reason for the differences between the two maps.

5 As for landslide susceptibility at global scale, Nadim et al. (2006) and Hong et al. (2007) have ever
6 made magnificent efforts on such topic. One global landslide susceptibility map (please refer to Fig. 7 in
7 Nadim et al. (2006)) has five levels (Levels 5, 6, 7, 8 and 9) as susceptible, while the map from this study
8 includes three levels (Levels 3, 4 and 5) as susceptible. In general, the susceptible areas of these two
9 maps are fairly similar except in Madagascar and the eastern Indo-China Peninsula.

10 Another global landslide susceptibility map (please refer to Fig. 3(a) in Hong et al. (2007)) has two
11 levels (Levels 4 and 5) as susceptible, compared to map in this study, which has three levels (Levels 3, 4
12 and 5) as susceptible. These two maps are similar over Asia, Europe and Africa. However, it is noted that
13 map of Hong et al. (2007) also differs from map of this study in that it shows high landslide susceptibility
14 in central and southern India, and low landslide susceptibility in equatorial islands such as Malaysia,
15 Indonesia, and the Philippines. We believe that the classification of landslide susceptibility of this
16 research can be more scientific and closer to the existing conditions.

17 With the development of global DEM products, DEM with finer resolution is now available to the
18 public. The NASA Shuttle Radar Topographic Mission (Jarvis et al., 2012) has provided digital elevation
19 data for over 80% of the globe. This data is currently distributed free of charge. The SRTM data is
20 available as 3 arc second (approx. 90m resolution) DEM covering the globe from 60°N to 60°S. The 1-
21 arc-second data product was also produced and now is available for all countries. To explore the
22 sensitivity of DEM on model result, experiments have also been performed when following all the
23 procedures stated above, but using SRTM 90m DEM as source of ~~topology~~ topography. As showed in
24 Table 56, landslide susceptibility model with 90m DEM had no significant difference (only an increase
25 about 0.005 in AUC) with those models using 1km DEM (AUC in modelling, from 0.8768 to 0.8818;
26 AUC in validation, from 0.8871 to 0.8929). When location precision of landslide is not that good, using
27 finer DEM cannot help to increase the accuracy of landslide susceptibility analysis. DEM with coarser
28 resolution (i.e. 1km DEM) is recommended as the topographical factor in global landslide susceptibility
29 mapping.

30 The accuracy of logistic regression model in this paper is quite high compared with that of similar
31 experiment that is performed at national scale (Lin et al., 2017) or local scale (Wang et al., 2016), which
32 really exceeds expectation. To have one single model to explain the occurrence of past landslides events
33 in global scale may be difficult, but the result of model in this paper shows that the factors and their
34 weights in this research can actually provide good explanation of global landslide occurrence in one
35 model.

36 For the incompleteness of landslide inventory in the global geological hazard database of this study,
37 the landslides included in this study may represent only a subset of the total landslides around the world.
38 Studying global landslide susceptibility in a more comprehensive and objective way requires a more
39 complete global landslide inventory. As for the weights of factor, actually they cannot provide adequate
40 accuracy when building landslide model in local scale. However, we have determined to compare this
41 research with those performed in local scale to investigate the rules of landslide occurrence in different
42 scales in the coming future.

43 The main focus of this research is global landslide susceptibility assessment, and hence the landslides
44 in database of this research should be representative on global scale, i.e. having large volume or causing

批注 [LL16]: Reviewer #1, R9

批注 [LL17]: Reviewer #1, R10

批注 [LL18]: Reviewer #1, R2

批注 [LL19]: Reviewer #1, R2

1 significant loss. The landslides in our database can meet such requirement and are either of large
2 magnitudes or causing severe life loss or economic loss, which are hence easily reported by news
3 agencies. The global landslide susceptibility map built on this database can inevitably underestimate the
4 landslide susceptibility in some sparsely populated areas or less developed areas. However, if we don't
5 following the guidelines, in our database there will be a large numbers of landslides that are occurred in
6 countries with good landslide catalogue and few in countries with poor landslide catalogue. Such model
7 may lead to overestimation of landslide susceptibility in countries with rich landslide records and
8 underestimation of landslide susceptibility in countries with poor landslide records. This may not be good
9 for improving the accuracy of the map of global landslide susceptibility. Hence we think that the landslide
10 database in our research is relatively high in representative and reliable. We will explore the use of big
11 data on Internet in building more comprehensive landslide database in our next research and tries to
12 enhance the studies of landslide susceptibility when landslide catalogues from various countries can be
13 easily accessed in the future.

批注 [LL20]: Reviewer #1, R4

14 15 **6. Conclusions**

16 This paper applies stepwise logistic regression model to study landslide susceptibility on global scale.
17 After investigating the explanatory factors for landslides in the existing literature, five explanatory
18 factors: extreme precipitation, lithology, relative relief, ground motion and soil moisture, are selected.
19 These factors are used to build a landslide susceptibility model through stepwise logistic regression based
20 on landslides recorded in a combined global landslide inventory. It is found that the five explanatory
21 factors perform well in explaining the occurrence of landslides on a global scale. Percentage correct in
22 confusion matrix of landslide classification during modeling ranges from 78.7% to 80.4%, with an AUC
23 value from 0.8685 to 0.8846. During validation, percentage correct in confusion matrix ranges from 79.9%
24 to 82.1%, with an AUC value from 0.8809 to 0.8933. The results from those datasets are similar, and the
25 coefficients and ranks of each explanatory factor are relatively stable, which suggests that the model is
26 both robust and accurate.

27 Existing studies of landslide susceptibility generally use topography as an explanatory factor (Budimir
28 et al., 2015). However, on a global scale, topography is not always the primary factor for landslide
29 occurrence. For example, Hong et al. (2007) gives priority to slope when building their global landslide
30 model, and friction has the highest regression coefficient in model for earthquake-induced landslides
31 (Nowicki et al., 2014). The present study shows that on global scale, soil moisture is the most important
32 factor, while topography (relative relief in this study) is secondary. Additionally, this study shows that
33 soil moisture has significantly explanatory power for landslide occurrence on a global scale. Therefore,
34 it may suggest that future work of landslide susceptibility should consider the influence of soil water
35 condition and long-term precipitation when studying global landslide susceptibility.

36 37 **Acknowledgments**

38 This work was supported primarily by the National Natural Science Funds of China (41271544), and
39 National Key Technology R & D Program of the Twelfth Five-Year Plan of China (No. 2012BAK10B03).

40 41 **References**

42 [Alimohammadlou, Y., Najafi, A., and Gokceoglu, C.: Estimation of rainfall-induced landslides](#)
43 [using ANN and fuzzy clustering methods: A case study in Saenen Slope, Azerbaijan province,](#)
44 [Iran, Catena, 120, 149-162, 10.1016/j.catena.2014.04.009, 2014.](#)

- 1 [Allison, P. D.: Logistic regression using the SAS system: theory and application, Wiley Interscience, New York, 2001.](#)
- 2
- 3 [Anbalagan, R.: Landslide hazard evaluation and zonation mapping in mountainous terrain, Eng. Geol., 32, 269-277, 10.1016/0013-7952\(92\)90053-2, 1992.](#)
- 4
- 5 [Atkinson, P. M., and Massari, R.: Generalised linear modelling of susceptibility to landsliding in the central Apennines, Italy, Comput. Geosci., 24, 373-385, 10.1016/s0098-3004\(97\)00117-9, 1998.](#)
- 6
- 7
- 8 [Ayalew, L., and Yamagishi, H.: The application of GIS-based logistic regression for landslide susceptibility mapping in the Kakuda-Yahiko Mountains, Central Japan, Geomorphology, 65, 15-31, 10.1016/j.geomorph.2004.06.010, 2005.](#)
- 9
- 10
- 11 [Ayalew, L., Yamagishi, H., and Ugawa, N.: Landslide susceptibility mapping using GIS-based weighted linear combination, the case in Tsugawa area of Agano River, Niigata Prefecture, Japan, Landslides, 1, 73-81, 10.1007/s10346-003-0006-9, 2004.](#)
- 12
- 13
- 14 [Bai, S. B., Wang, J., Lu, G. N., Zhou, P. G., Hou, S. S., and Xu, S. N.: GIS-based logistic regression for landslide susceptibility mapping of the Zhongxian segment in the Three Gorges area, China, Geomorphology, 115, 23-31, 10.1016/j.geomorph.2009.09.025, 2010.](#)
- 15
- 16
- 17 [Bednarik, M., Magulová B., Matys, M., and Marschalko, M.: Landslide susceptibility assessment of the Kraľovany–Liptovský Mikuláš railway case study, Physics and Chemistry of the Earth, Parts A/B/C, 35, 162-171, 2010.](#)
- 18
- 19
- 20 [Bouysse, P.: Explanatory Notes: The Geological Map of the World at 1: 50 000 000 \(the third edition\), Commission for the Geological Map of the World publishing, <http://ccgm.org/img/cms/Expl%20Notes%20Geol%20Map%20World.pdf>, 2010.](#)
- 21
- 22
- 23 [Brenning, A.: Spatial prediction models for landslide hazards: review, comparison and evaluation, Nat. Hazards Earth Syst. Sci., 5, 853-862, 2005.](#)
- 24
- 25 [Budimir, M. E. A., Atkinson, P. M., and Lewis, H. G.: A systematic review of landslide probability mapping using logistic regression, Landslides, 12, 419-436, 10.1007/s10346-014-0550-5, 2015.](#)
- 26
- 27
- 28 [Caine, N.: The rainfall intensity-duration control of shallow landslides and debris flows, Geografiska Annaler, 62A, 23-27, 1980.](#)
- 29
- 30 [Carrara, A., Cardinali, M., Detti, R., Guzzetti, F., Pasqui, V., and Reichenbach, P.: GIS techniques and statistical models in evaluating landslide hazard, Earth. Surf. Proc. Land., 16, 427-445, 1991.](#)
- 31
- 32
- 33 [CGMW \(Commission for the Geological Map of the World\): Geological Map of the World at 1: 25 000 000, <http://ccgm.org/en/maps/93-carte-geologique-du-monde-a-125-000-000-9782917310045.html>, 2010.](#)
- 34
- 35
- 36 [Chang, K. T., Chiang, S. H., and Hsu, M. L.: Modeling typhoon- and earthquake-induced landslides in a mountainous watershed using logistic regression, Geomorphology, 89, 335-347, 10.1016/j.geomorph.2006.12.011, 2007.](#)
- 37
- 38
- 39 [Chau, K. T., and Chan, J. E.: Regional bias of landslide data in generating susceptibility maps using logistic regression: Case of Hong Kong Island, Landslides, 2, 280-290, 10.1007/s10346-005-0024-x, 2005.](#)
- 40
- 41
- 42 [Chauhan, S., Mukta, S., and Arora, M. K.: Landslide susceptibility zonation of the Chamoli region, Garhwal Himalayas, using logistic regression model, Landslides, 7, 411-423, 10.1007/s10346-010-0202-3, 2010.](#)
- 43
- 44

- 1 [Costanzo, D., Chacon, J., Conoscenti, C., Irigaray, C., and Rotigliano, E.: Forward logistic](#)
2 [regression for earth-flow landslide susceptibility assessment in the Platani river basin \(southern](#)
3 [Sicily, Italy\). *Landslides*, 11, 639-653, 10.1007/s10346-013-0415-3, 2014.](#)
- 4 [Cruden, D. M., and Varnes, D. J.: Landslide types and processes. in: Turner, A. K., and Schuster, R.](#)
5 [L. \(eds.\), *Landslides investigation and mitigation*, National Academy, Washington, 1996.](#)
- 6 [Dai, F. C., and Lee, C. F.: Landslide characteristics and slope instability modeling using GIS.](#)
7 [Lantau Island, Hong Kong, *Geomorphology*, 42, 213-228, 10.1016/s0169-555x\(01\)00087-3,](#)
8 [2002.](#)
- 9 [Dhakal, A. S., Amada, T., and Aniya, M.: Landslide hazard mapping and the application of GIS in](#)
10 [the Kulekhani watershed, Nepal, *Mt. Res. Dev.*, 19, 3-16, 10.2307/3674109, 1999.](#)
- 11 [Ercanoglu, M., and Gokceoglu, C.: Assessment of landslide susceptibility for a landslide-prone area](#)
12 [\(north of Yenice, NW Turkey\) by fuzzy approach, *Environ. Geol.*, 41, 720-730,](#)
13 [10.1007/s00254-001-0454-2, 2002.](#)
- 14 [Erener, A., and Duzgun, H. S. B.: Improvement of statistical landslide susceptibility mapping by](#)
15 [using spatial and global regression methods in the case of More and Romsdal \(Norway\).](#)
16 [Landslides, 7, 55-68, 10.1007/s10346-009-0188-x, 2010.](#)
- 17 [Farahmand, A., and AghaKouchak, A.: A satellite-based global landslide model, *Nat. Hazards Earth*
18 \[Syst. Sci.\]\(#\), 13, 1259-1267, 10.5194/nhess-13-1259-2013, 2013.](#)
- 19 [Felicísimo, A., Cuartero, A., Remondo, J., and Quiros, E.: Mapping landslide susceptibility with](#)
20 [logistic regression, multiple adaptive regression splines, classification and regression trees, and](#)
21 [maximum entropy methods: a comparative study, *Landslides*, 10, 175-189, 10.1007/s10346-](#)
22 [012-0320-1, 2013.](#)
- 23 [Galli, M., and Guzzetti, F.: Landslide vulnerability criteria: A case study from Umbria, central Italy,](#)
24 [Environ. Manage., 40, 649-664, 10.1007/s00267-006-0325-4, 2007.](#)
- 25 [Gao, J.: A summary of world natural disasters in 1998, *Disaster reduction in China*, 9, 52-58, 1999.](#)
26 [\(Published in Chinese\)](#)
- 27 [Giardini, D., Grinthal, G., Shedlock, K. M., and Zhang, P.: The GSHAP global seismic hazard map,](#)
28 [in: Lee, W., Kanamori, H., Jennings, P., and Kisslinger, C. \(eds.\) *International handbook of*](#)
29 [earthquake and engineering seismology, International Geophysics Series 81 B, Academic Press,](#)
30 [Amsterdam, 1233-1239, 2003. <http://www.gfz-potsdam.de/GSHAP>.](#)
- 31 [Guzzetti, F., Carrara, A., Cardinali, M., and Reichenbach, P.: Landslide hazard evaluation: a review](#)
32 [of current techniques and their application in a multi-scale study, Central Italy, *Geomorphology*,](#)
33 [31, 181-216, 10.1016/s0169-555x\(99\)00078-1, 1999.](#)
- 34 [Guzzetti, F., Reichenbach, P., Ardizzone, F., Cardinali, M., and Galli, M.: Estimating the quality of](#)
35 [landslide susceptibility models, *Geomorphology*, 81, 166-184,](#)
36 [10.1016/j.geomorph.2006.04.007, 2006.](#)
- 37 [Hong, Y., Adler, R., and Huffman, G.: Use of satellite remote sensing data in the mapping of global](#)
38 [landslide susceptibility, *Nat. Hazards*, 43, 245-256, 10.1007/s11069-006-9104-z, 2007.](#)
- 39 [Jarvis, A., Reuter, H., Nelson, A., and Guevara, E.: Hole-filled SRTM for the globe version 4,](#)
40 [technical report, the CGIAR-CSI SRTM 90m Database, <http://srtm.csi.cgiar.org>, 2012.](#)
- 41 [Kawabata, D., and Bandibas, J.: Landslide susceptibility mapping using geological data, a DEM](#)
42 [from ASTER images and an Artificial Neural Network \(ANN\), *Geomorphology*, 113, 97-109,](#)
43 [10.1016/j.geomorph.2009.06.006, 2009.](#)
- 44 [Kirschbaum, D. B., Adler, R., Hong, Y., Hill, S., and Lerner-Lam, A.: A global landslide catalog for](#)

1 [hazard applications: method, results, and limitations, Nat. Hazards, 52, 561-575,](#)
2 [10.1007/s11069-009-9401-4, 2010.](#)

3 [Lee, S.: Application of logistic regression model and its validation for landslide susceptibility](#)
4 [mapping using GIS and remote sensing data journals, Int. J. Remote Sens., 26, 1477-1491,](#)
5 [10.1080/01431160412331331012, 2005.](#)

6 [Lee, S., and Min, K.: Statistical analysis of landslide susceptibility at Yongin, Korea, Environ. Geol.,](#)
7 [40, 1095-1113, 2001.](#)

8 [Lin, Q., Wang, Y., Liu, T., Zhu, Y., and Sui, Q.: The vulnerability of people to landslides: a case](#)
9 [study on the relationship between the casualties and volume of landslides in China,](#)
10 [International journal of environmental research and public health, 14, 212, 2017.](#)

11 [Liu, C., Li, W., Wu, H., Lu, P., Sang, K., Sun, W., Chen, W., Hong, Y., and Li, R.: Susceptibility](#)
12 [evaluation and mapping of china's landslides based on multi-source data, Natural Hazards, 69,](#)
13 [1477-1495, 2013.](#)

14 [Mathew, J., Jha, V. K., and Rawat, G. S.: Landslide susceptibility zonation mapping and its](#)
15 [validation in part of Garhwal Lesser Himalaya, India, using binary logistic regression analysis](#)
16 [and receiver operating characteristic curve method, Landslides, 6, 17-26, 10.1007/s10346-008-](#)
17 [0138-z, 2009.](#)

18 [Matsuura, S., Asano, S., and Okamoto, T.: Relationship between rain and/or meltwater, pore-water](#)
19 [pressure and displacement of a reactivated landslide, Eng. Geol., 101, 49-59,](#)
20 [10.1016/j.enggeo.2008.03.007, 2008.](#)

21 [Mora, S., and Vahrson, W.: Macrozonation methodology for landslide hazard determination, Bull.](#)
22 [Assoc. Eng. Geol., 31, 49-58, 1994.](#)

23 [Nadim, F., Kjekstad, O., Peduzzi, P., Herold, C., and Jaedicke, C.: Global landslide and avalanche](#)
24 [hotspots, Landslides, 3, 159-173, 10.1007/s10346-006-0036-1, 2006.](#)

25 [Nowicki, M. A., Wald, D. J., Hamburger, M. W., Hearne, M., and Thompson, E. M.: Development](#)
26 [of a globally applicable model for near real-time prediction of seismically induced landslides,](#)
27 [Eng. Geol., 173, 54-65, 10.1016/j.enggeo.2014.02.002, 2014.](#)

28 [Pachauri, A. K., and Pant, M.: Landslide hazard mapping based on geological attributes, Eng. Geol.,](#)
29 [32, 81-100, 10.1016/0013-7952\(92\)90020-y, 1992.](#)

30 [Regmi, N. R., Giardino, J. R., McDonald, E. V., and Vitek, J. D.: A comparison of logistic](#)
31 [regression-based models of susceptibility to landslides in western Colorado, USA, Landslides,](#)
32 [11, 247-262, 10.1007/s10346-012-0380-2, 2014.](#)

33 [Schneider, U., Becker, A., Finger, P., Meyer-Christoffer, A., Rudolf, B., and Ziese, M.: GPCC full](#)
34 [data reanalysis version 6.0 at 0.5 ° monthly land-surface precipitation from rain-gauges built](#)
35 [on GTS-based and historic data, 10.5676/DWD_GPCC/FD_M_V6_050, 2011.](#)

36 [Swets, J. A.: Measuring the accuracy of diagnostic systems, Science, 240, 1285-1293, 1988.](#)

37 [Terlien, M. T. J., Van Asch, T. W. J., and Van Westen, C. J.: Deterministic modelling in GIS-based](#)
38 [landslide hazard assessment, in: Carrara, A., and Guzzetti, F. \(eds.\) Geographical information](#)
39 [systems in assessing natural hazards, Kluwer Academic Publishing, The Netherlands, 57-77,](#)
40 [1995.](#)

41 [Umar, Z., Pradhan, B., Ahmad, A., Jebur, M. N., and Tehrany, M. S.: Earthquake induced landslide](#)
42 [susceptibility mapping using an integrated ensemble frequency ratio and logistic regression](#)
43 [models in West Sumatera Province, Indonesia, Catena, 118, 124-135,](#)
44 [10.1016/j.catena.2014.02.005, 2014.](#)

1 [USGS: GTOPO30 readme, https://lta.cr.usgs.gov/GTOPO30, 2012.](https://lta.cr.usgs.gov/GTOPO30)
2 [Van Den Eeckhaut, M., and Hervás, J.: State of the art of national landslide databases in Europe and
3 their potential for assessing susceptibility, hazard and risk, *Geomorphology* 139 \(140\), 545–
4 558, 2012.](#)
5 [Van Den Eeckhaut, M., Vanwalleghem, T., Poesen, J., Govers, G., Verstraeten, G., and
6 Vandekerckhove, L.: Prediction of landslide susceptibility using rare events logistic regression:
7 A case-study in the Flemish Ardennes \(Belgium\), *Geomorphology*, 76, 392-410,
8 10.1016/j.geomorph.2005.12.003, 2006.](#)
9 [Van Den Eeckhaut, M., Hervas, J., Jaedicke, C., Malet, J. P., Montanarella, L., and Nadim, F.:
10 Statistical modelling of Europe-wide landslide susceptibility using limited landslide inventory
11 data, *Landslides*, 9, 357-369, 10.1007/s10346-011-0299-z, 2012.](#)
12 [Varnes, D. J.: Landslide hazard zonation: a review of principles and practice, UNESCO, Paris, 1984.](#)
13 [Wang, Y., Song, C., Lin, Q., and Li, J.: Occurrence probability assessment of earthquake-triggered
14 landslides with Newmark displacement values and logistic regression: The Wenchuan
15 earthquake, China, *Geomorphology*, 258, 108-119, 2016.](#)
16 [Willmott, C. J., and Feddema, J. J.: A more rational climatic moisture index, *Prof. Geogr.*, 44, 84-
17 88, 1992.](#)
18 [Wu, W. M., and Sidle, R. C.: A distributed slope stability model for steep forested basins, *Water
19 Resour. Res.*, 31, 2097-2110, 10.1029/95wr01136, 1995.](#)
20

带格式的: 两端对齐, 缩进: 左侧: 0 厘米, 悬挂缩进: 1.35 字符,
首行缩进: -1.35 字符, 无孤行控制

1 **Table 1** Brief summary of explanatory factors in landslide susceptibility assessment for regional scale
 2 and global scale
 3

Factors	Geographic scale of study	
	Regional	Global
topography	slope gradient, slope aspect, elevation, plan curvatures, profile curvatures (1)*, slope morphology (2), standard deviation of slope gradient (6)	Median, minimum, and maximum slope values from DEM (10), topography index (11), slope angle (12), elevation (13)
geology	lithology (1), density of geological boundaries (3), distance to geological boundaries (3), weathering depth (4), tectonic uplift (9), geological age (6)	lithology (12)
hydrology	proximity to drainage lines (2), water conditions (4), drainage density (5), distance from river, stream power index (SPI) (7)	drainage density (13)
soil	texture, material, soil thickness (5), topographic wetness index (TWI)(7), soil type, soil moisture (6)	material strength (10), soil wetness (10), soil moisture (12), soil type (13), soil texture (13)
precipitation	rainfall (7), total monthly precipitation (8), annual precipitation (9)	precipitation rates from rainfall accumulations in the past (11), extreme monthly rainfall with 100 years return period (12)
land cover	vegetation cover (2,4), age, diameter and density of timber for vegetation (5), land use/cover (7), road construction (8)	land use and land cover (11,13)
ground motion	peak ground acceleration (7), earthquake and seismic shaking (8)	peak ground acceleration and peak ground velocity (10)

*Numbers in the table indicate related studies, they are: (1) Ayalew et al., 2004; (2) Dai and Lee, 2002; (3) Kawabata and Bandibas, 2009; (4) Ercanoglu and Gokceoglu, 2002; (5) Lee and Min, 2001; (6) Van Den Eeckhaut et al., 2012; (7) Umar et al., 2014; (8) Alimohammadlou et al., 2014; (9) Erener and Duzgun, 2010; (10) Nowicki et al., 2014; (11) Farahmand and AghaKouchak, 2013; (12) Nadim et al., 2006; (13) Hong et al., 2007.

4
5

1 **Table 2** Input variables used in logistic regression analysis

2

Dependent variables: landslide location	Data provider	Map details
World Geological Hazard Inventory	ADREM, BNU	Point
Global landslide inventory	NASA	Point
Independent variables	Sources	Map details
Relative relief (unit: m)		
Classification method: natural breaks (1. <=80; 2. 80-264; 3. 264-520; 4. 520-844; 5. 844-1226; 6. 1226-1672; 7. 1672-2232; 8. 2232-2982; 9. 2982-4024; 10. >4024)	GTOPO and SRTM DEM	30/3 arc-second
Lithology		
Classification method: refer to Nadim et al. (2006) (0. Undifferentiated facies, Ophiolitic complex, Endogenous rocks, Oceanic crust; 1. Extrusive volcanic rocks: Precambrian, Proterozoic, Paleozoic and Archean, Endogenous rocks (plutonic and/or metamorphic): Precambrian, Proterozoic, Paleozoic and Archean; 2. Old sedimentary rocks: Precambrian, Archean, Proterozoic, Paleozoic, Extrusive volcanic rocks: Paleozoic, Mesozoic, Endogenous rocks: Paleozoic, Mesozoic, Triassic, Jurassic, Cretaceous; 3. Sedimentary rocks: Paleozoic, Mesozoic, Triassic, Jurassic, Cretaceous, Extrusive volcanic rocks: Mesozoic, Triassic, Jurassic, Cretaceous, Endogenous rocks: Meso-Cenozoic, Cenozoic; 4. Sedimentary rocks: Cenozoic, Quaternary, Extrusive volcanic rocks: Meso-Cenozoic; 5. Extrusive volcanic rocks: Cenozoic)	Geological map of the world at a 1:25,000,000 by Commission for the Geological Map of the World (CGMW) and UNESCO	Polygon (rasterized into 0.01 arc-second)
Soil moisture index		
Classification method: refer to Nadim et al. (2006) (1. -1.0 ~ -0.6; 2. -0.6 ~ -0.2; 3. -0.2 ~ +0.2; 4. +0.2 ~ +0.6; 5. +0.6 ~ +1.0)	Willmott and Feddema (1992)	0.5 arc-second
Monthly extreme rainfall with return period of 100 years (unit: mm)		
Classification method: natural breaks (1. <=55; 2. 55-150; 3. 150-250; 4. 250-365; 5. 365-500; 6. 500-650; 7. 650-850; 8. 850-1100; 9. 1100-1650; 10. >1650)	calculated using historical precipitation grid data over 50 years (from 1961 to 2010) from the GPCP Full Data Reanalysis	0.5 arc-second
PGA with an exceedance probability of 10% over 50 years (unit: m*s ⁻²)		
Classification method: refer to Nadim et al. (2006) (1. 0.00-0.50; 2. 0.51-1.00; 3. 1.01-1.50; 4. 1.51-2.00; 5. 2.01-2.50; 6. 2.51-3.00; 7. 3.01-3.50; 8. 3.51-4.00; 9. 4.01-4.50; 10. >4.50)	Global seismic hazard map created by the Global Seismic Hazard Assessment Program (GSHAP) of the International Lithosphere Program (ILP)	0.1 arc-second

3

4

1 **Table 3** Example of landslide inventory in World Geological Hazard Inventory created by ADREM,
 2 BNU
 3

ID	Hazard type	Date	Country	Continent	Location	Longitude/Latitude	Death	Lost	Injured	Location precision (°)	Sources
000159	Debris flow	2005.6.1	U. S.	North America	Laguna Beach, Los Angeles, California	33°32'32.63"N 117°46'18.10"W	0	0	2	0.05	Sina News
000168	Landslide	2010.11.4	Costa Rica	South America	San Antonio, San José	9°55'37.48"N 84°04'55.24"W	20	12	0	0.1	Xinhua News
000403	Debris flow	2010.8.7	China	Asia	Zhouqu, Gansu	33°47'10.56"N 104°22'7.24"E	1463	302	2244	0.1	Xinhua News
000465	Landslide	2008.6.29	Côte d'Ivoire	Africa	Abidjan	5°20'10.74"N 4°1'39.90"W	7	0	4	0.01	Sina News

4

1 **Table 4** Model results of stepwise logistic regression for each dataset

2
3

Dataset	Intercept	Soil moisture	PGA	Lithology	Relative relief	Extreme precipitation	AIC [†]	Modeling		Validation	
								Percentage correct	AUC	Percentage correct	AUC
Set 1	-5.7898***	0.5567***	0.1196***	0.1885***	0.3583***	0.2798***	2511.2	0.801	0.8755	0.810	0.8914
Set 2	-5.7047***	0.5528***	0.1958***	0.1245**	0.3159***	0.2957***	2468.4	0.797	0.8789	0.821	0.8933
Set 3	-5.9134***	0.5980***	0.1803***	0.1583***	0.3312***	0.2924***	2421.8	0.804	0.8846	0.799	0.8812
Set 4	-5.6525***	0.5432***	0.1704***	0.1073**	0.3344***	0.2977***	2483.8	0.798	0.8766	0.804	0.8809
Set 5	-5.3490***	0.5426***	0.1663***	0.1100**	0.3022***	0.2625***	2564.5	0.787	0.8685	0.814	0.8886
Average	---	---	---	---	---	---	2489.9	0.797	0.8768	0.810	0.8871

[†]These statistics of AIC are based on the model with intercept and covariates

**Coefficients are significant at 1% confidential level

*** Coefficients are significant at 0.1% confidential level

1 **Table 5** Numbers of landslides and non-landslides in each dataset.

Continent	Landslides	Dataset 1		Dataset 2		Dataset 3		Dataset 4		Dataset 5	
		Modelling (70%)	Validation (30%)	Modelling (70%)	Validation (30%)	Modelling (70%)	Validation (30%)	Modelling (70%)	Validation (30%)	Modelling (70%)	Validation (30%)
Asia	1205	847:348	358:163	848:394	357:157	838:383	367:155	849:364	356:162	847:393	358:165
Africa	69	55:317	14:129	50:307	19:114	47:324	22:130	47:315	22:129	49:302	20:126
Europe	121	94:211	27:70	86:212	35:116	87:200	34:91	88:206	33:88	85:251	36:106
North America	425	274:235	151:98	296:235	129:98	298:226	127:107	286:230	139:110	286:195	139:83
South America	133	93:189	40:98	86:174	47:75	99:179	34:78	97:193	36:80	96:144	37:64
Oceania	52	40:103	12:44	37:81	15:42	34:91	18:41	36:95	16:33	40:118	12:58
Total	2005	1403:1403	602:602	1403:1403	602:602	1403:1403	602:602	1403:1403	602:602	1403:1403	602:602

Numbers in left represent numbers of landslides, numbers in right represents numbers of non-landslides.

2

批注 [LL21]: Reviewer #1, R6

带格式的: 字体: 10 磅

带格式表格

带格式的: 字体: 10 磅

带格式的: 字体: 10 磅

带格式的: 字体: 10 磅

带格式的: 字体: 10 磅

带格式的: 字体: 10 磅

带格式的: 字体: 10 磅

带格式的: 字体: 10 磅

带格式的: 字体: 8 磅

带格式表格

1 **Table 5-6** Results of model based on global SRTM DEM (90m)
 2
 3

Dataset	Intercept	Soil humidity	PGA	Lithology	Relative relief	Extreme precipitation	AIC [†]	Modeling		Validation	
								Percentage correct	AUC	Percentage correct	AUC
Set 1	-5.8362***	0.5359***	0.1173***	0.1876***	0.3585***	0.2809***	2495.9	0.802	0.8767	0.818	0.8939
Set 2	-5.7546***	0.5441***	0.1980***	0.1222**	0.3151***	0.2947***	2436.6	0.799	0.8826	0.828	0.8980
Set 3	-5.9650***	0.5850***	0.1791***	0.1604***	0.3328***	0.2919***	2384.0	0.815	0.8888	0.810	0.8861
Set 4	-5.7457***	0.5503***	0.1682***	0.1060**	0.3393***	0.2925***	2437.6	0.808	0.8822	0.806	0.8856
Set 5	-5.5849***	0.5618***	0.1629***	0.1236**	0.3093***	0.2745***	2479.4	0.799	0.8785	0.815	0.9008
Average	---	---	---	---	---	---	2446.7	0.805	0.8818	0.815	0.8929

[†]These statistics of AIC are based on the model with intercept and covariates


**Coefficients are significant at 1% confidential level

*** Coefficients are significant at 0.1% confidential level

1
2

Fig.1 Landslide location in the combined landslide database


批注 [LL22]: Reviewer #1, R10, R11



3

1
2

Fig.2 Comparison of landslide overlay in this research and that in existing study




批注 [LL23]: Reviewer #1, R5
带格式的: 字体: 非加粗
带格式的: 字体: (默认) Arial
带格式的: 居中
带格式表格
带格式的: 字体: (默认) Arial

3
4

带格式的: 字体: 非加粗


1 Fig.2-3 ROC curve of modeling process



2
3
4

1 Fig.3.4 ROC curve of validation process

2




3

4

5

1
2

Fig.4-5 Global-scale landslide susceptibility map




3


批注 [LL24]: Reviewer #1, R10, R11
带格式的: 左

1
2
3

Fig. 6 Comparison of existing studies with the related parts of this study.



(a) Comparison of European landslide susceptibility map (from Van Den Eeckhaut et al. 2012) with the related part in this study's map



(b) Comparison of China landslide susceptibility map (from Liu et al. 2013) with the related part in this study's map

4
5

带格式的: 字体: 加粗

带格式的: 字体: 10 磅

带格式的: 字体: 10 磅

带格式的: 居中

带格式的: 字体: 10 磅

带格式的: 字体: 10 磅

带格式的: 居中

带格式的: 英语(英国)